

The City of Pinson requests quotes for the following scopes of work in regards to the final work and utility connection to the storm shelter located at 5320 Miles Springs Road as follows:

- 1) Install a Five (5) foot wide sidewalk two sides of the building, ADA compliant.
- 2) Asphalt Paving and marking as shown to connect sidewalk to existing paving as shown. The 20 feet including the ADA spaces must be ADA compliant, 2% grade maximum, the sloped to meet existing
- 3) Install approximately 120 feet of 4 inch PVC sewerage line from the front of the shelter to existing septic line. No pump required. Install approximately 120 feet of 1" PEX water supply line from an existing "Tee" near the former pump house. The water supply line shall be installed at a radius so as to avoid the septic field of the fire station.
- 4) Install a 100 am electric meter and ground rod to connect to the Main Disconnect switch that is in place and installed.

Trade permits for items 3 and 4 are required. There is a county building permit in place for reference.

Trade permit items require licensed tradesmen for those scopes.

Please remit quotes by March 31. Quote scopes separately if pricing more than one item. A City of Pinson business license is required, as well as insurance document copies, general liability and workman's comp, to be awarded.

Questions or clarifications may be requested of Hoyt Sanders, Mayor. Attached find reference drawing. Conditions may be verified on location at 5320 Miles Spring Road.

Thank you for your interest.

Sincerely,
Hoyt Sanders
Mayor

